KOLAR DIVISION.

Dated 8th April 1907.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Kolar Division, up to 18th April 1907, for constructing an Anglo-Vernacular School at Malur. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1907.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Kolar between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed. The rates tendered should include royalty on stones, etc., removed from the Government lands, to be paid to the Government.

4. Each tender must be accompanied by a deposit of Rs. 150 in Currency Notes or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing Anglo-Vernacular School at Malur;" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

ABSTRACT.

Items of work	Per	Quantity
Earthwork, excavating and filling basement	C. yd.	142
Concrete in chunam	C. ft.	1,279
Stone in chunam foundation and basement	"	3,414
Do superstructure	"	6,493
Do arch work	"	372
Burnt stone slabs, dressed	"	999
Burnt stone pillars with caps bases, dressed, etc.	No.	4
Rolled steel beam angle iron reepers and round iron rod including railway fare up to Bangalore	Cwt.	65·39
Carriage, railway fare and hoisting charges of above iron work.	L. S.	Rupees
Folding angle iron reepers, drilling holes in reepers and rafter revet and riveting complete each joist	Each joist	693
Drilling holes in rafters for bolting at top and anchoring at bottom	Each	46
Do do for verandah ...	"	18
Bolts to bind the top of rafter and vally rafters	"	11
Do do for verandah	"	6
Anchor plates 9"×9"×¼" and holding down bolts 18" long and ¾" diameter	"	32
Fish plate with 2 bolts, drilling 3 holes in rafter and 3 holes in fish plate threading both ends of the rods and providing with nut, etc., complete	"	9
Fish plates and vally rafters with bolts at junction at ridge ...	"	4
Painting iron works	Sqr.	30·50
Roofing with bare Mangalore tiles	"	30·50
Ridge tiles set in mortar	R. ft.	133
Zinc sheet for vally	"	60
Teakwood pannelled doors with hinges, etc., complete ...	S. ft.	404
Do windows with glazed shutters inside, iron bars, etc, complete	"	286
Do ventilators with glazed shutters, etc., complete ...	"	179
Do for lights over windows with do ...	"	9
Chunam plastering inside	Sqr.	63·66
Do pointing outside	"	43·24
Whitewashing	"	63·66
Flooring with Cuddapah slabs over 3" concrete and cement pointing	"	17·39
Silicate painting of doors and windows	"	19·08
Moulding over windows and ventilators...	R. ft.	192
Chunam borders at gable 6"×3"	"	90
Levelling the ground	L. S.	Rupees
Opening road and tunnel constructing	"	"
Iron hold fasts to doors and windows	No.	204
Galvanized zinc sheet ornamental cave board with paintings ...	R. ft.	332

K. KRISHNAIENGAR, *Exec. Engr., Kolar Dn.*